CHITALDRUG DISTRICT.

Abstract Notification, dated 18th January 1933.

The attention of intending purchasers is drawn to pages 93 and 94, Part VI of the *Mysore Gazette*, dated 26th January 1933, notifying the resale of Tangadi and Kakke barks of several units of the Chitaldrug District for 1931-33.

B. N. IYENGAR,
District Forest Officer.

ENGINEERING DEPARTMENT.

MYSORE PUBLIC WORKS DEPARTMENT.

HEAD-QUARTER RANGE, BANGALORE.

Abstract Notification, dated 25th January 1933.

The attention of the public is invited to the Notification calling for tenders for "Construction of Town Hall in Bangalore City" published on pages 109 to 113 of Part VI of *Mysore Gazette*, dated 26th January 1933.

The last date for receiving tenders is 20th February 1933.

B. NARASIMHIENGAR,
Assistant Engineer,
Headquarter Range.

GOVERNMENT OF MYSORE, ELECTRICAL DEPARTMENT.

Notification, dated 28—30th January 1933.

SALE OF SCRAPS.

Sealed tenders for the purchase of the following scrap materials will be received in the office of the undersigned up to 2 P.M., on the 27th February 1933.

About 20 tons of Copper Scrap.
About 4½ tons of Lead Scrap.
About 6½ tons of Alluminium Scrap.
About ¾ ton of Brass Scrap.

1. The scrap materials will be available for inspection either at the Central Stores near Binny Mills, Bangalore City or at the Electrical Stores at the Office of the Power and Lighting, Mysore.

2. The tenders should be superscribed "tenders for the purchase of scraps due at 2 P.M. on 27th February 1933" and should be accompanied with an earnest money of Rs. 500.

The earnest money should be sent separately by registered post and should be either in currency notes or cheques drawn on the Mysore Bank, Bangalore, or the Imperial Bank of India, Bangalore.

3. The undersigned reserves to himself the right to refuse the highest or any tender whole or in part without assigning any reasons therefor or sell only a part of the scrap available.

4. The deposit of the successful tenderer will be retained, and he will be required to execute an agreement and furnish immediately a further deposit of one fourth of the amount of the value of the quantity offered to be sold.

5. Payment in full will have to be made for the quantities of scrap removed from our stores and the amount of the earnest money and the further deposit made will be adjusted towards the close of the whole transaction.

6. Delivery will be in the Central Stores near City Railway Station, or at any other sub-stores of this Department wherever the material is available.

7. Failure to comply with the above conditions will entail the forfeiture of the amounts deposited together with the earnest money and the scrap copper will be resold at the risk of the tenderer who will have no claim to profits if any, that might accrue in the resale, but will be liable to reimburse the Department all losses entailed in the resale.

8. Arrangements will be made to refund the earnest money of the unsuccessful tenderer as soon after the tenders are opened and are decided upon as possible.

Notification dated 28th January 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Chief Electrical Engineer, Bangalore, up to 2 P.M., on the 17th February 1933, for constructing Electrical Buildings at Maddur Town.

1. The tenders will be opened in public at 2 P.M., on 17th February 1933. The work should be completed within *four months* and the monthly progress should not be less than Rs. 1,500.

2. The plan, detailed estimates and the conditions may be seen at the Office of the Chief Electrical Engineer, Bangalore, on all working days during the office working hours.

3. The tenders should be accompanied by a statement in the form attached showing the rates at which different items specified will be executed. The rates should be in figures as well as in words.

4. Each tender must be accompanied by a deposit of Rs. 300 or Government Promissory

for the rejection of any tender. The Chief Electrical Engineer also reserves the right to accept or reject any portion of the tender.

6. Within eight days of the award of the tender, the successful tenderer will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful tenderer will be posted on the Notice Board of the Chief Electrical Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The construction work should be started within a week from the date of notification of acceptance.

10. Water for construction should be got at the contractor's own expense.

11. Specifications for works are those recognised by the Mysore Public Works Department and Marroyts' specifications.

12. The contractor should be bound by the conditions of the schedule of contract of the Electrical Department.

Statement showing the approximate quantities for constructing Station Office and stores at Maddur.

Sl. No.	Items	Unit	Quantity	Rate
				Rs. a. p.
1	Earth work excavation and filling in basement ...	Cyd.	39	
2	Stone jelly in lime concrete foundation ...	Cft.	361	
3	Stone in lime foundation and basement including through stones every 6 ft. apart in every course.	"	869	
4	Burnt brick in clay superstructure ...	"	1298	
5	Burnt brick in mortar superstructure ...	"	144	
6	Stone slabs 6" thick roughly dressed and fixed in mortar.	Sft.	177	
7	Stone slabs 3" thick exposed parts one line dressed and set in mortar.	"	7	
8	Brick in mortar, pillars 1·1/8' square and 9'-9" high including stone base and capital and cement plastering ½" thick all round.	1 Item	4	
9	Chunam plastering 2 coats	Sqr.	29	
10	Chunam pointing with thread lines ...	"	1·88	
11	White and colour washing two coats ...	"	31·00	
12	Plain brick cornice 6" projection as per design.	Rft.	158	
13	Brick in mortar plain parapet wall 9" thick as per design.	"	155	
14	Chunam moulding in front of wall between pillars.	1 Item	3	
15	Chunam moulding 6"x½" all round ventilators ..	Rft.	77	
16	Cuddapah slab flooring 1½" thick on 3" lime concrete and cement pointed with thread lines.	Sqr.	1·94	
17	First Class Mangalore tile flooring on 3" thick concrete and cement pointed.	"	4·06	
18	Roofing with Madras Terrace 9" thick including plastering, etc., complete.	"	6·75	
19	Steel work fixed complete (Tata Make) with two coats of painting.	Cwt.	44·0	
20	Teakwood door panelled 1½" thick shutters with fixtures, etc., complete.	Sft.	92	
21	Teakwood glazed windows 1¼" thick with iron bars 5/8" dia. with fixtures, etc., complete shutters to be in 4 leaves.	"	70	
22	Teakwood ventilators glazed shutters 1" thick with iron bars.	"	27	
23	Chocolate painting 2 coats	Sqr.	12·87	
24	Fixing wire-gauze shutters with teak battens complete.	Sft.	63	
25	Rain water down pipe fixed complete 3" diameter	Rft.	178	

Statement showing the approximate quantities of work for constructing One Block of Cooly Quarters and an Operator's Quarters with 2 units of Latrine at Maddur.

Serial No.	Items	Unit	Operator's Quarters	Cooly sheds	2 Units of Latrine
1	Earth work excavation and filling in basement.	Cyd.	24	18	8
2a	Concrete stone jelly in lime mortar ...	Cft.	306	219	...
b	Coursed rubble stone masonry in clay foundation and basement with bond stones in each course 6 ft. apart	"	547	440	260
c	Burnt brick in clay superstructure ..	"	1666	1512	...
d	Stone slabs 4" thick set in Lime mortar ...	Sft.	108	66	...
e	Stone slab 6" thick for pillars including polly cutting fixed complete.	"	..	12	...
f	Do 6" thick do ...	"	5	...	..
g	Chunam plastering two coats ...	Sqr.	44·06	29·75	9·82
h	Chunam pointing with thread lines ...	"	1·03	1·00	1·12
i	White and colour washing 2 coats ...	"	45·10	29·70	10·94
j	Constructing sinks in bath rooms ..	No.	1	2	..
k	Mortar and pestle fixed complete ...	"	1	2	...
l	6" plain cornice brick in mortar ..	Rft.	56	40	...
m	6" x 3" chunam patty over roof ...	"	12	18	...
3a	First class Mangalore tile roofing on teak wood reepers complete.	Sqr.	7·89	7·68	...
b	Ridge tile set in mortar	Rft.	24	25	...
c	Ventilating tiles set in mortar ...	No.	2	8	...
4a	Honney wood wrought and put up with 2 coats of wood oil.	Cft.	29·35	24·40	....
b	Teak wood doors with Honney wood battened shutters 1" thick with bolts and hinges complete.	Sft.	137	39	...
4c	Teak wood windows with Honney wood battened shutters 1" thick with bars, etc., complete.	Sft.	50	39	...
d	Teak wood ventilators	"	18	...	...
e	Teak wood planks 1" thick with wood oiling.	"	34	...	...
f	Chocolate painting two coats ...	Sqr.	4·78	1·00	...
5	Flooring on 3" concrete and cement plastering ½" thick finished smooth and even.	"	4·50	4·00	...
6	Binding wall 1·1/8' x ¾' brick in mortar and chunam plastered.	Rft.	56	40	...
7	Burnt bick in mortar superstructure ...	Cft.	...	...	392
8	Cement plastering ½" thick ...	Sqr.	....	...	1·58
9	Tar washing 2 coats	"	...	...	1·26
10	Flooring with 3" thick concrete and cement plastering ½" thick.	"	...	....	·76
11	Providing galvanised iron sheet tubs 12" x 6" with handles, etc., complete with tarring.	No.	...	...	6

V. R. COWSIK,
For *Chief Electrical Engineer.*

BANGALORE DIVISION.

Notification dated 27th January 1933.

Notice is hereby given that sealed quotations will be received at the Office of the Executive Engineer, Bangalore Division, up to2 P.M. on 15th February 1933, for Improving Isthur Amanikere Reg. No. 103 of Hoskote Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1934.